

Iscritto all'Ordine degli Ingegneri di Torino, Matricola 10842F  
Via Monte Grappa 32a - 12048 Sommariva del Bosco (CN)

OGGETTO:  
PROGETTO DEFINITIVO / ESECUTIVO

|               |               |
|---------------|---------------|
| /             | TAV_02        |
| Codice Lavoro | Codice Tavola |

|            |                     |
|------------|---------------------|
| 11/06/2018 | 1:200 - 1:50 - 1:30 |
| Data       | Scala               |

**CONSOLIDAMENTO STRUTTURALE PORZIONE DI MURO DEL PIAZZALE DELLA  
PARROCCHIA - Via Salita Boglione, Sommariva del Bosco (CN)**

PROGETTO DEFINITIVO / ESECUTIVO

**COMUNE DI SOMMARIVA DEL BOSCO**

TIMBRO E FIRMA:

**ING. FABIO CAPELLO**  
Ordine degli Ingegneri di Torino, Matr. 10842F  
Via Monte Grappa 32a, 12048 SOMMARIVA DEL BOSCO (CN)

TIMBRO E FIRMA:

**NOTE:**  
VERIFICARE LE QUOTE IN CANTIERE - L'IMPRESA E' TENUTA AL CONTROLLO DELLE MISURE E AL  
CONFRONTO CON IL PROGETTO ARCHITETTONICO

Technical drawing showing a cross-section of a wall and foundation. The drawing includes the following elements:

- Existing Micropiles:** A row of micropiles at the top, labeled "Berlinese di micropali esistente".
- New Wall:** A new wall is shown below the micropiles, labeled "Nuovo muro in c.a." (New wall in concrete).
- Foundation:** The wall is founded on a base, with a level marked as  $\pm 0.00$ .
- Dimensions:**
  - Vertical dimensions on the left: 1225 (total height from base to micropile level) and 1185 (height from base to wall top).
  - Vertical dimensions on the right: 50 (height from base to wall top) and 50 (height from wall top to micropile level).
- Labels:**
  - "PIAZZALE PARROCCHIA" (Parish Square) is labeled above the wall.
  - "Micropalo Ø 193 L=8 m" is labeled for the micropiles on both sides.
- Section Line:** A red line labeled "A" indicates the section line.

**Armatura trave testa palo 40x40 cm**

Stafie Ø10/20 L=156

34 34 34

40

n.4 Ø 16

Micropalo Ø 193 L=8 m

Sezione micropali (n°6)

Ø193 mm

TUBO 193 x 6 mm

**Vista frontale trave palo**

150

40

50 50

Micropalo Ø 193 L=8 m

n°2 Ferri ancoraggio Ø20 L=155

45

60 60